



SUPSALV's Mission - What We Do...

Underwater Ship Repair

(N43 & Customer Funded)

- □ Ship Design for Underwater Repair
- □ ~100 Operations Per Year

 Avoid need for emergency dry-dock
- □ Up to 20:1 Return on Investment



Search & Recovery (N43 & Customer Funded)

- **□** Air France Flight 447
- ☐ Minneapolis, MN Bridge Collapse
- □ Space Shuttle Columbia & Challenger
- **□** Ehime Maru
- □ E-2C Hawkeye North Arabian Sea
- □ ~15 Operations Per Year



Ship Salvage, Towing, and Heavy Lift

(N43 & Customer Funded)

- **■** USS PORT ROYAL (CG 73) Grounding
- □ Port of San Francisco Dry Dock (2013)
- ☐ Hurricanes Katrina & Rita (475 Ships Salvaged)
- **■** USS COLE (DDG 67)
- □ ~20 Operations Per Year


Oil Spill Response (N45)

- □ Large Inventory Sized to Act as Tier II/III OSRO for Navy Ships/Facilities
- Emphasis on Transportability in Austere Environments
- **□** Ex USS CHEHALIS Fuel Removal
- Hurricanes Katrina and Rita
- Operation Iraqi Freedom
- **□** Deepwater Horizon Oil Spill



Diving/Certification (N87)

- USN Diving Manual & Decompression Table used worldwide
- □ Navy Experimental Diving Unit One of a kind in the world
- □ Equipment Development & Procurement
- Certification Authority for all of DoD







The Event:

October 29, 2012

90 mph winds

The Mission:

Dewatering

The Problem:



The transit tunnels were 100-185 feet below the surface; each tunnel with millions of gallons of water.










Hurricane Sandy









SUPSALV engaged support through existing contracts to immediately mobilize pumps, support equipment and personnel to the NY/NJ area.

DonJon Marine: creatively decided to deliver the dewatering and ancillary equipment to Battery Park HQ site via barge flotilla










Hurricane Sandy

Facility / Location	Agency / Owner	Est. Volume to Pump
Battery Underpass / West Street Underpass	NYC DOT	10 m gal
Brooklyn Battery Tunnel	MTA - B&T	64 m gal
PATH Train Tunnel	PANYNJ	200 m gal
World Trade Center	PANYNJ	200 m gal
14th St Tunnel	MTA - NYCT	3.5 m gal
53rd Street Tunnel	MTA - NYCT	2 m gal
Montague Tunnel	MTA - NYCT	25 m gal
Amtrak Substation Kearny, NJ	AMTRACK	5.4 m gal
South Ferry Station	MTA - NYCT	20 m gal









- TOTAL ESTIMATE POL ONBOARD 15, 700 gal
 - 14, 600 gal Diesel Fuel (DFM)
 - 500 gal hydraulic fluid
 - 600 gal L/O in sumps and storage tanks
- No indication of catastrophic hull penetration






















































Accomplishments:

- oCarried-out at sea 85 miles from nearest port
- Water-logged wood hull increased weight significantly
- ONo release of hazmat or oil
- No structural collapse
- Reduced environmental impact

