

Appendix H

Example Construction-Phase Checklists for Inspector and Contractor Training

Introduction and Purpose

DOT representatives have identified construction phase issues as a common causes of infiltration BMP failure. This appendix contains simple construction-phase checklists that DOTs can use to support training of construction inspectors and contractors related to construction of infiltration BMPs. These checklists address key issues that can occur during the construction phase. They are intended to serve as a quick reference for a site inspector or contractor in identifying and avoiding these issues.

The checklists contained in this Appendix address the following key construction objectives:

1. Prevent and Remediate Compaction of Underlying Soil
2. Prevent Compaction of Engineered Filtration Soil (Bioretention Soil, Amended Soil)
3. Prevent and Remediate Siltation During Construction
4. Prevent and Remediate Erosion and Siltation During Establishment Period

The general construction checklist provides general recommended practices for addressing these issues. These recommendations apply to the site regardless of BMP type.

The BMP-specific construction checklist provides more specific recommendations for that apply to one or more BMPs. The checklist indicates the BMP(s) to which these recommendations apply.

General Construction Checklist

Objective 1: Prevent and Remediate Compaction of Underlying Soil

Key issues	<ul style="list-style-type: none"> • Construction equipment • Material stockpiling • Highway traffic detours
Recommended Practices	
1. Stake off infiltration areas with construction fence or other barriers	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
2. Mark infiltration areas on all construction sheets, such as haul routes, stockpiling areas, traffic detours	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
3. Do not allow equipment, vehicle traffic or stock piling in these areas	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
4. Make equipment operators aware of infiltration areas as part of construction meetings	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
5. Excavate to finish grade of infiltration areas <u>after</u> most other construction is complete	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
6. Remediate infiltration areas via tilling and/or scarification to at least 12 inches depth after excavation to finish grade and after equipment will no longer access the BMP	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
7. Use construction-phase infiltration tests to confirm that infiltration rates have been restored	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>

Objective 2: Prevent Compaction of Engineered Filtration Soil (Bioretention Soil, Amended Soil)

Key issues	<ul style="list-style-type: none"> • Placement methods • Material moisture when placed
Recommended Practices	
1. Place media from the side of BMP whenever possible	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
2. If equipment access to BMP is needed to place media, use low ground pressure equipment	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
3. Do not place media if wet or if underlying soils are wet	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
4. Lightly compact to approximately 75 to 80 percent relative compaction (or hydro-consolidate via flooding with water)	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
5. Use construction-phase infiltration tests on a pilot plot to confirm that placement methods yielding adequate media infiltration rates	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
6. Repeat testing of media infiltration rate at appropriate intervals through placement of media	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>

General Construction Checklist

Objective 3: Prevent and Remediate Siltation During Construction

Key issues	<ul style="list-style-type: none"> • Sediment in construction runoff to BMP • Erosion from graded BMP slopes or upper BMP cells
Recommended Practices	
1. Do not use infiltration BMPs for construction-phase sediment control	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
2. If BMPs must be used, then partially excavate during construction (stop 2 feet short of final grade) and then continue excavation to finish grade after construction	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
3. When BMPs are commissioned for completed phases, carefully control sediment track-out from phases of ongoing construction	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
4. If siltation occurs, over excavate to at least 1 feet and backfill with selective fill materials	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
5. Use infiltration testing to ensure infiltration rates have been restored after rehabilitation	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
6. If BMP must be excavated to finish grade to serve as temporary sediment pond, consider lining pond with a sacrificial liner, such as an impermeable plastic membrane, that can be removed and disposed after construction.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>

Objective 4: Prevent and Remediate Erosion and Siltation During Establishment Period

Key issues	<ul style="list-style-type: none"> • Erosion from partially established tributary areas • Erosion from bed of BMP (upper cells resulting in sediment of lower cells)
Recommended Practices	
1. Do not allow water to flow to BMPs until the site is fully stabilized	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
2. Initiate vegetation establishment well in advance of project completion to allow stabilization prior to BMP commissioning	
3. For vegetated BMPs, install soil amendment and vegetation well in advance of project completion to allow vegetation and root structure to establish before stormwater loading – including side slopes	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
4. Provide irrigation, if needed, to promote more rapid vegetation establishment	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>
5. Keep environmental and construction permits open until site has full established to allow for access to perform remediation	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>

BMP-Specific Construction Checklist

Project Name _____		Bioretention with underdrain	Bioretention no underdrain	Infiltration Trench	Infiltration Basin	Vegetated Conveyance	Permeable Shoulders	Media Filter Drain	Dispersion	Underground Infiltration
BMP Types _____										
Location _____										
Contractor Name _____										
Reviewer Name _____										
Inspection Date and Time _____										
A. EXCAVATION										
1. Facility excavated to the dimensions and at the location shown on the approved plan. Excavation must be free of any standing water.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x	x	x	x		x
2. Facility excavated from the sides to avoid compacting the existing soil.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x	x	x	x		x
3. Bottom was scarified prior to placement of rock and sand or media (and sides if bioretention, infiltration trenches)	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x		x			
4. Bottom of excavation within design slope range per the approved plan	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>		x	x	x		x	x		x
5. Excavation sidewalls are consistent with the approved plan	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x				x		x
B. PIPING AND DRAINAGE										
1. Inlet protection was installed at the inflow, if applicable, per the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x		x	x		x
2. Overflow pipe or catch basin was installed at the elevation/depth that is specified on the approved plan	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
3. Underdrain pipe material and size are as shown on the approved plan, if applicable.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x			x		x	x		x
4. Underdrain was constructed at the depth/elevation specified in the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x			x		x	x		
5. Underdrain piping was laid flat or on a positive slope toward the outlet as shown on the approved plans.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x			x		x	x		
6. Underdrain pipe perforations as shown in the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x			x		x	x		
7. Clean-out access and/or observation ports are installed to view subsurface water level	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x			x			x
8. Double-washed crushed aggregate or clean stone was installed around the underdrain pipe.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x			x		
9. Manhole/maintenance catch basin installed at elevations as specified on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>									x
10. Chambers were installed as shown on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>									x
C. GRADING										
1. Channel protection and/or level spreader was provided at infiltration (or bio) inlets as specified on the approved plan	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x					
2. Spillway or top of berm was constructed to design elevation and dimensions per the approved plan	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x					
3. Side slopes of infiltration basin or bioretention buffer area (above design top of bioretention soils media) is no steeper than 3:1 (unless approved by geotechnical engineer)	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x					

BMP-Specific Construction Checklist

Project Name _____		Bioretention with underdrain	Bioretention no underdrain	Infiltration Trench	Infiltration Basin	Vegetated Conveyance	Permeable Shoulders	Media Filter Drain	Dispersion	Underground Infiltration
BMP Types _____										
Location _____										
Contractor Name _____										
Reviewer Name _____										
Inspection Date and Time _____										
4. Side slopes installed as noted on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>					x				
5. Bottom of channel or basin graded as noted on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x	x				
6. Installation of check dams (as needed) as shown on the approved plan (swales and linear bioretention)	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x			x	x			
7. Grading of level spreader and filter strip or media filter drain promotes sheet flow	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>							x	x	
D. SOIL MEDIA										
1. Bioretention soil media was installed in accordance with the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
2. Bioretention soil media was spread out using an excavator from the side of the excavation area to minimize compaction.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
3. Bioretention soil media was installed when it was optimally moist (not wet or dry) and there was no precipitation.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
4. Bioretention soil media was placed within bioretention facilities during the same day that the area was excavated to prevent contamination if a runoff event occurred prior to placement of soil media.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
5. Media permeability was tested to verify placement methods did not compromise permeability	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
E. VEGETATION										
1. Vegetation planted per the numbers and species specified on the approved planting plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x	x				
2. Plants occupy about 50% of the total surface area of the bioretention soil media.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
3. Individual plant spacing follows the recommendations on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
4. Trees were planted only around the perimeter of the facility in the native soil, and not in the bioretention soil media.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x							
5. Phase construction to allow vegetation establishment prior to commissioning BMP	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x	x		x	x	
6. Stabilize side slopes of BMP prior to placing media or excavating to finish grade	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x		x					
7. Topsoil and/or compost amendments are applied evenly over the pervious area, and in quantities and depths specified in the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>								x	
8. Vegetation applied at a rate to achieve 90% germination and as shown on the approved plan.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>					x			x	

BMP-Specific Construction Checklist

Project Name _____		Bioretention with underdrain	Bioretention no underdrain	Infiltration Trench	Infiltration Basin	Vegetated Conveyance	Permeable Shoulders	Media Filter Drain	Dispersion	Underground Infiltration
BMP Types _____										
Location _____										
Contractor Name _____										
Reviewer Name _____										
Inspection Date and Time _____										
9. Seed mix specified on the approved plan has been applied.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>					x			x	
10. Biodegradable erosion control blanket was installed over the previous area for protection while seed germination occurs.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>					x			x	
F. EROSION AND SEDIMENT CONTROL										
1. Run-on protections are in place around this facility if there are areas that slope toward this facility or that could potentially discharge sediment to this facility.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x	x	x	x	x	x
2. BMP does not receive construction site runoff.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x	x	x	x	x	x
3. Silt fence or fiber rolls were placed around the BMP perimeter to prevent sediment contamination prior to full stabilization of the tributary drainage area.	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x					
4. Sacrificial protective liner is included in BMP during construction and removed after site is stabilized	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x		x	x		x
5. Sediment is remediated by over-excavating to 1 foot below infiltrating surface and backfilling with select permeable material	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	x	x	x	x		x	x		x
6. Construction stormwater must not enter BMPs with subsurface infiltration surface after they are placed (remediation not possible)	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>			x			x			x
G. General Comments and Notes:										

Bibliography

1. California Stormwater Quality Association. California Stormwater BMP Handbook: New Development and Redevelopment. 2003. Fact Sheet containing design guidance, construction and maintenance information for BMPs. Available online at <https://www.casqa.org/resources/bmp-handbooks/new-development-redevelopment-bmp-handbook>
2. Delaware Sediment and Stormwater Programs Post Construction Stormwater BMP Standards and Specifications. Contains construction checklists for post-construction inspection of permanent stormwater facilities. Available online at <http://www.dnrec.delaware.gov/swc/pages/sedimentstormwater.aspx>
3. Low Impact Development Center, Inc. Evaluation of Best Management Practices for Highway Runoff Control. NCHRP Project 25-20(01). 2006. Manual intended to provide the highway engineer with selection guidance toward implementation of BMPs and LID facilities for control of stormwater quality in the highway environment. Includes detailed schematics, cost tables for different items in each BMP. <https://www.coralreef.gov/transportation/evalbmp.pdf>
4. Low Impact Development Center, Inc. Low Impact Development Manual for Southern California: Technical Guidance and Site Planning Strategies. 2010. resource that can be used to guide communities in the development of design, construction, and maintenance standards and specifications, as well as codes and ordinances, which can support their water quality management and regulatory compliance programs. Available online at <https://www.casqa.org/resources/lid/socal-lid-manual>
5. Massachusetts Stormwater Handbook, Volume 2, Chapter. 2. Stormwater Best Management Practices (MassDEP). Contains highly detailed BMP Fact Sheets, with figures, design considerations, construction and maintenance guidance. <http://www.mass.gov/eea/docs/dep/water/laws/i-thru-z/v2c2.pdf>
6. New Jersey Stormwater Best Management Practices Manual. Fact Sheet 9.1 – Bioretention Systems. Chapter 9 contains detailed design, construction, maintenance; sizing and applicability of bioretention systems, including with and without underdrain. Available online at http://www.njstormwater.org/bmp_manual/NJ_SWBMP_9.1.pdf
7. Prince George’s County Bioretention Manual. 2007. Environmental Services Division, Department of Environment Resources. The Prince George’s County, Maryland. This manual builds on previous manuals and further identifies methodologies, practices, and examples of bioretention. Changes that were made focus primarily on four parameters: (1) functionality and application; (2) pollutant removal efficiency; (3) aesthetics and site integration; and (4) design simplification for cost containment. Mostly applicable to local applications of bioretention. Available online at http://www.ct.gov/deep/lib/deep/p2/raingardens/bioretention_manual_2009_version.pdf
8. Virginia Department of Conservation and Recreation. Virginia DCR Stormwater Design Specification. 2011. Fact sheet on infiltration practices including design guidance, construction and feasibility. Excellent figures and schematics. Available online at <http://chesapeakestormwater.net/category/publications/design-specifications/>