

REPORTS ON EXPERIMENTS WITH CONTINUOUS REINFORCEMENT IN CONCRETE PAVEMENTS—CALIFORNIA

THOS. E. STANTON, *Materials and Research Engineer, California Division of Highways*

SYNOPSIS

The California continuous reinforced concrete pavement project was designed primarily to study the stresses in the steel reinforcing and the crack incidence in an 8-in. uniform thickness pavement slab with the steel centrally placed in the depth of the slab, as well as longtime performance with relation to riding qualities.

One grade of steel was specified, but two grades were used owing to the fact that the contractors purchased the steel from two vendors, and one vendor had, through a misunderstanding, rolled a harder grade than the other.

Advantage was taken of this happenstance to use one grade for one-half of the mile long test section and the other grade in the other half.

The lower strength bars were spaced 4-in. c/c and the higher strength on 5-in. centers.

The bars were $\frac{3}{4}$ -in. deformed bars. Therefore, the percentage of steel for the 4-in. spacing was 0.63 percent and for the 5-in. spacing 0.50 percent.

The paving contract as a whole was 4.7 mi. long, consisting of four lanes divided—two contiguous lanes in each direction. The construction was in 12-ft. lanes, the contiguous lanes being tied together with machine bolts. A standard 5-sack mix was used.

Numerous test specimens (in the form of cylinders and beams) were cast during the progress of the work for the usual compression and modulus of rupture tests and compressive and dynamic modulus of elasticity.

In addition to the compression and modulus of rupture tests, specimens were cast for tension tests. The tension test procedure and tests results are described. The procedure may not have been theoretically sound but remarkably consistent results were secured and, in the absence of any better test procedure is deemed of sufficient accuracy to justify including as a part of this report.

SR-4 strain gages were used to measure the stress in the steel.

The subgrade on the project consisted of a cement treated base. No subgrade failures or distress in the concrete pavement due to movement of the subgrade have developed to date (over $1\frac{1}{2}$ years after construction).

Cores were cut at 28 days and one year. There are some fairly wide differences in the strength of the concrete poured on different days. These differences can be attributed, in part at least, to differences in water cement ratio. At times the construction engineers were concerned about the proper distribution of the concrete through and around the steel reinforcing (maximum coarse aggregate $2\frac{1}{2}$ in.). The tendency, therefore, was to increase the slump to insure what was felt to be a desirable consistency to avoid hang-up on the steel and honeycomb.

However, observation of the cores cut from the wet and dry concrete, as well as of the concrete adjacent to the side headers did not disclose any material deficiency in placement of the dryer concrete.

Initial shrinkage crack count records were made early in the morning following each day's pour. As anticipated numerous fine transverse cracks have developed. The report includes the crack record up to one and one half years.

Three-inch expansion joints were provided at each end of the mile test section with the ends of the concrete unrestrained. Numerous length change points were installed in the pavement throughout its length, as well as at each end of the test section.

Therefore, local and overall length change data are available.

Initial and subsequent pavement roughness measurements were made with the Hveem Profilograph.

Temperatures of the top, center, and bottom of the concrete pavement slab were measured with thermocouples during construction as well as subsequently at the time other measurements were made.

In the fall of 1938 the Public Roads Administration and the Indiana State Highway Commission initiated the construction of a number of experimental sections of reinforced concrete pavement.¹

Supplementing the Indiana studies, in the fall of 1947 the Illinois Division of Highways and the New Jersey State Highway Department undertook similar constructions² and during 1949 at the instigation of the U. S. Bureau of Public Roads the California Division of Highways constructed a one-mile section of continuously reinforced concrete pave-

ment in Solano County in the vicinity of the town of Fairfield.

Figure 1 shows a general layout of the project. Figure 2 shows information regarding grades, location of test section, dates pavement was constructed, etc.

The project in general consists of a four-lane divided highway over new alignment. Each side of the divided highway consists of two 12-ft. wide contiguous lanes of 8-in. thick portland cement concrete. The contiguous lanes are tied together with $\frac{5}{8}$ -in. diameter




Figure 1. Location of Test Project

ment in Solano County in the vicinity of the town of Fairfield.

Eastern State projects contain a number of test sections with variable size, spacing and position of the steel. It was decided to confine the California project to the limited number of variables herein recited. There is, therefore, no opportunity to compare directly with the three earlier projects described in Highway Research Board *Proceedings* except where the conditions are reasonably similar.

The California project was designed primarily to study the stresses in the steel reinforcing and the crack incidence in an 8-in. uniform thickness continuously reinforced pavement slab, with the steel centrally placed in the depth of the slab, as well as long time performance with relation to riding qualities.

The project is part of U. S. Route 40 connecting the metropolitan areas of the San Francisco Bay Region and Sacramento. The

30-in. long tie bolts on 30-in. centers. There is a tongue and groove joint at the junction of the two lanes.

The territory traversed is generally flat valley land used for grazing. The native soil along the project is of adobe of somewhat variable composition, having a California Bearing Ratio ranging from 2 to 20 percent and expansions ranging from 1.7 to 10.8 percent and Atterberg limits of L.L. 36 to 43 and P.I. 16 to 23. A 10-in. layer of gray volcanic ash (Tuff) was placed as imported borrow over the adobe. The Tuff has an average compacted weight of 65 lb. per cu. ft. at 25 to 30 percent optimum moisture and a California Bearing Ratio ranging from 150 to 200 percent. As the Tuff had little cementing value the upper 4 in. of this subgrade material was treated with 3.5 percent of cement by weight of dry material to avoid washing, shifting, pumping, and step-offs.

The imported base material was specified for the project as a whole, including the reinforced test section.

The pavement concrete was Class B (5 sack)

¹ Proceedings, Highway Research Board, Vol. 19 (1939) and Vol. 29 (1949).

² Proceedings, Highway Research Board, Vol. 29 (1949).

with 2½ in. maximum size coarse aggregate. Outside of the mile-long reinforced section, weakened plane joints were placed at 15-ft. intervals with no expansion joints except at each end of the continuously reinforced test section. The surface of the newly laid pavement was kept moist by applying water with a fog nozzle until the application of a light gray pigmented curing compound.

Traffic—The average daily traffic over this road amounts to approximately 12,000 vehicles of all types. Therefore, the traffic on the test section over which only the west bound traffic

dors and one vendor had, through a misunderstanding, rolled a harder grade than the other (Fig. 3).

Advantage was taken of this happenstance to use one grade for one half of the mile-long test section and the other grade in the other half, the reinforcement being continuous throughout.

The lower strength bars were spaced 4 in. c/c and the higher strength on 5-in. centers.

The amount of ½-in. reinforcing for one 12-ft. lane per mile and average characteristics of the steel are given in Table 1.




Figure 2. Plan of Test Project

passes is approximately one-half this amount or an average of 6,000 per day.

Description of Test Section—The one mile of continuously reinforced test section with 4-in. unrestrained expansion joints at each end was constructed in the two contiguous west-bound lanes. The longitudinal reinforcement consisted of ½-in. old type deformed steel bars on 4-in. and 5-in. centers placed at the center of the slab. Transverse ½-in. steel bars were placed on 5-ft. centers. No weakened plane joints were placed in the reinforced section except as noted in the portions in which stress measuring SR-4 gages had been installed.

One grade of steel was specified but two grades were used owing to the fact that the contractors purchased the steel from two ven-


The reinforcing steel was furnished to the job in 30-ft. lengths. All splices were staggered and lapped 40 diameters or 20 in. for the ½-in. steel. The longitudinal reinforcing steel was carried continuously through all construction joints and through the transition between Sections 1 and 2 (Fig. 4).

Curing—Curing of the concrete was with a light gray pigmented solution under specifications similar to the Bureau of Reclamation specifications for white pigmented curing solutions, but lightly tinted to reduce potential glare.

Order of Construction—Paving of the north (traffic) lane of the test section was started on May 23, 1949 and finished on May 25, an average run of 1427 feet or 521 cubic yards

per day for the 12 ft. wide by 8 in. thick concrete slab.

reinforcing continuously across the transverse construction joint between daily runs. It was



TYPE OF DEFORMATION



COLUMBIA

JUDSON PACIFIC

TEST RESULTS

JUDSON PACIFIC

Heat No	No of Tests	Elongation 8" %	Elastic Limit P.S.I.	Ult Strength P.S.I.	Chemical Analysis %			
					C	Mn	Phos	Sul
1519	6	16.75	55710	87015	.41	.59	.005	.038
2134	6	17.05	54675	86450	.42	.52	.007	.046
1451	5	16.25	54440	83250	.40	.53	.005	.032
1489	6	19.25	52665	81975	.39	.53	.006	.037
2132	6	17.20	52950	81925	.40	.53	.006	.043
Average		17.30	54090	84120	.40	.54	.006	.039

COLUMBIA

54078	5	11.97	71725	121260	.56	.85	.016	.035
71568	6	11.23	69625	116195	.60	.93	.011	.027
71948	6	12.11	69160	118390	.58	.88	.012	.030
54508	5	10.57	73460	122670	.61	.87	.013	.035
54078	5	10.23	73010	124750	.55	.98	.020	.036
71988	5	11.92	74630	124440	.56	.74	.014	.028
Average		11.67	71935	121250	.58	.88	.014	.033

Figure 3. Characteristics of 1/2-in. Deformed Steel Reinforcing Bars Used in Tests

The specifications required the contractor to start paving each lane of the test section at the beginning of the day and to carry the

required that pouring the second lane should match the operations on the first lane; namely, to start the second lane in the morning at the

same station as the first lane and to quit at the end of the first day in the second lane at the same station as the first day in the first lane. This procedure was followed on both lanes for the first day and the start of the second day.

However, on the second day of the second lane, the speed of the contractor's operations had increased to such an extent that he was able and was permitted to complete the entire mile the second day; the second day's run being 3060 lineal feet of pavement.

TABLE 1

Section	Spacing	Steel	Steel	Average	
				Elastic Limit	Ultimate Strength
	in.	%	tons per sq. ft.	psi.	psi.
1	4	0.02	71.4	54,090	84,120
2	5	0.5	58.3	71,985	121,270




Figure 4. Reinforcing Steel in Place on Base

The atmospheric and concrete temperatures during the paving operations were moderate to high.

Tests Units—

A. *Longitudinal Movement.* Reference points for measuring the overall longitudinal movement of the pavement on the subgrade were installed in both lanes at the beginning and end of the test section. Additional units were installed in the traffic lane in both the standard concrete and the reinforced concrete at 100, 200, 300, 400, 600 and 800 ft. from each end of the test section. Three additional points were installed, one at the midpoint of

the test section and the other two at 100 ft. each side of the midpoint.

The reference points consisted of an open bottom steel box fitted with a weatherproof lid and a reference rod driven 2 feet into the subgrade. Measurements of the longitudinal movement were made with calipers and micrometers with an accuracy of 0.01 in. Movement up to one year is shown in Figure 5.

B. *Joint and Crack Width Measurements.* Brass inserts were placed, in the fresh concrete, across each expansion joint in both the traffic and passing lanes for measuring the opening and closing of the joints. Brass inserts were also placed across the first 14 weakened plane joints, in the traffic lane only, in the standard unreinforced concrete, extending from each end of the test section. Additional brass inserts were placed across a few formed weakened plane joints in the reinforced sections at points where the stress in the reinforcing steel was to be measured. Readings were made with a micrometer to an accuracy of 0.002 in.

At an early age before the formation of the bulk of the intermediate shrinkage cracks, the maximum measured crack opening was 0.04 in. at an interior construction joint. At the weakened planes the maximum at the same age was 0.017 in. The crack widths of all of the early formed cracks decreased with further intermediate cracking, even with a 40-deg. drop in temperature.

Additional brass inserts on 48-in. centers were placed in the traffic lane for the first 100 ft. from the expansion joints in the reinforced steel section to catch and measure changes in width of any naturally occurring transverse cracks. Readings were made with a special micrometer to an accuracy of 0.005 in.

C. *Stresses in Reinforcing Steel Measured with SR-4 Gages.* SR-4 gages were installed on selected reinforcing bars at two locations in each section in each lane; a total of eight groups (Figs. 8, 9, 10 and 11). The arrangement of reinforcing bars and gages was such that part of the gages measured stress in the reinforcing steel at a formed weakened joint and part the stress in the reinforcing steel in uncracked concrete. Natural cracks have formed at some gage locations.

The SR-4 type A-1 gages were attached at the laboratory to 20-ft. lengths of the reinforcing bars; all loose scale and deformations

being first removed from the bars to obtain a smooth surface at the location of gage attachment. The surfaces were thoroughly cleaned and gages attached with Cellulose cement. General Electric Company 16 A.W.G. $\frac{3}{4}$ -in. Flamenol insulated wire was soldered to each gage lead. The gages were then waterproofed with 3M EC711 air drying rubber cement after a minimum of 7 days drying period. The rubber cement waterproofing was applied

sembly was then wired to the reinforcing steel with the center line of the assembly at the elevation of the reinforcing steel, mid-depth of the pavement (Fig. 6).

Lead wires from all SR-4 gages were brought out to the shoulder and attached to terminal boxes. Readings were taken with a standard Baldwin SR-4 indicator connected to the lead wires.

A total of 186 active SR-4 gages and 72




Figure 5. Longitudinal Pavement Movement

in 7 to 10 thin coats, allowing a 24-hr. drying period between each coat. A final protective coat of 2 layers of $\frac{1}{2}$ lapped 3-M Scotch 33 electrical tape was placed over the gages (Fig. 6).

Each gage was calibrated at the Laboratory after attachment to the bar by stressing the bar by increments to just below the yield point and taking strain readings on the gages at each increment of load.

The temperature compensation units consisted of gages cemented to 4-in. lengths of reinforcing steel with lead wires soldered to the gages and then waterproofed, the assembly then being placed in a 6-in. length of 1-in. steel tube conduit with 2 disks of $\frac{1}{2}$ in. Celotex placed in each end and sealed with Petrolastic. The whole temperature compensating as-




Figure 6. SR-4 Gages on Reinforcing Steel

temperature compensation gages were installed in the test sections.

The insulation resistance of the active gages

TABLE 2

Age after Installation in Concrete Pavement	Percentage of SR-4 Gages With Indicated Or Greater Resistance To Ground							
	Active Gages				Temp. Comp. Gages			
	Resistance to Ground megohms							
	10	25	50	100	10	25	50	100
3 Days	100	100	100	100	100	100	100	100
6 Mo.	87	73	40	15	99	99	99	99
12 Mo.	74	25	4	0	99	99	99	99
18 Mo.	5	0			99	99	99	99

pensating gages still showing a high resistance to ground indicates that the method used to protect the lead wires and waterproof the gages was adequate for at least eighteen months when suitable protection is provided. This would indicate that some better method of protection should be provided for protecting the active gages from the action of the concrete.

The insulation resistance to ground at various intervals after installation in the concrete was as shown in Table 2.

It will be noted that at the end of 12 mo. at least 74 percent of the active gages still




Figure 7. Average Stress in Reinforcing Steel

decreased materially within the first six months and excessively after the first year, but the temperature compensation gages have, in general, shown a high resistance to ground up to 18 months.

The high percentage of temperature com-

measured 10 megohms or greater resistance to ground. The resistance to ground deteriorated until at 18 mo. only 5 percent of the active gages measured 10 megohms or greater to ground. The insulation resistance of the temperature compensating gages has remained

high, with 99 percent having a measured resistance to ground of 100 megohms or better at 18 mo.

The average measured stress in the reinforcing steel, between cracks, increased steadily (Fig. 7) irrespective of temperature and moisture conditions in the pavement at the time readings were taken. Readings taken at 18 months (not shown on Fig. 7) were exceptionally high.

frequently much above the ultimate strength of the reinforcing bars.

At early ages (less than 3 mo.) the readings on pairs of SR-4 gages opposite each other on the same reinforcing bar (Figs. 8, 9, 10 and 11) were in agreement within 10 percent. There was, however, a noticeable increase in the variations in readings at 3 mo. and at 6 mo. Many of the pairs of gages varied 100 percent. This, plus the drop in insulation re-




Figure 8. Plan of Placement of SR-4 Gages on Steel and Crack Formation—Sections 1-A and 1-C

The average measured stress in the reinforcing steel, across formed cracks, increased with diminishing temperatures to a high at age of 6 mo. (Fig. 7) and dropped only slightly with a raise in temperature at age of 13 mo. Measurements taken at 18 mo. (not shown on Fig. 7) were beyond any reasonable figure.

Seventy-four percent of the readings made at 18 mo. exceeded the range of the SR-4 indicator. The calculated stress, based on calibrations made below the elastic limit, was

sistance of the active gages, indicates that stress readings beyond the 3 mo. period are not reliable and indicate stresses far in excess of those actually developed in the steel.

Now that the active gages are inoperative, it is in order to cut some cores through the steel bars to inspect the condition of the bars at the points of highest indicated stress.

D. *Concrete Temperature Measurements.* Iron constantan thermocouples were installed; (1) one inch up from the bottom;

(2) on the reinforcing steel in the center of the concrete slab, and (3) one inch down from the top of the pavement slab. This installation was repeated at enough gage locations to secure a temperature record of the concrete at the time the concrete was placed. Temperature records have been made each period at which readings have been taken on the SR-4 gages as well as at any other times measure-

described. Remarkably consistent tension strength results were secured. Cores were cut and tested at 28 days and at one year.

There are some fairly wide differences in the strength of the concrete poured on different days, but more particularly between the two lanes which were constructed fifteen days apart. These differences can be attributed, in part at least, to differences in temperature at




Figure 9. Plan of Placement of SR-4 Gages on Steel and Crack Formation—Sections 1-B and 1-D

ments have been made of the opening and closing of the joints.

Concrete Tests—Numerous test specimens (in the form of cylinders and beams) were cast during the progress of the work for the usual compression and modulus of rupture tests and compressive and dynamic modulus of elasticity.

In addition to the compression and modulus of rupture tests special 6- by 10-in. concrete cylinders were tested in tension. The tension test procedure and test results are hereinafter

the time of placing and in part to differences in water cement ratio. At times the construction engineers were concerned about the proper distribution of the concrete through and around the steel reinforcing (maximum size coarse aggregate $2\frac{1}{2}$ in.). The tendency, therefore, was to increase the W/C ratio and consequently the slump to insure what was felt to be a desirable consistency to avoid honeycomb and hang-up on the steel. After observing some honeycomb along the edges of the first constructed lane the water cement ratio




Figure 10. Plan of Placement of SR-4 Gages on Steel and Crack Formation—Sections 2-A and 2-C




Figure 11. Plan of Placement of SR-4 Gages on Steel and Crack Formation—Sections 2-B and 2-D

was increased slightly during the construction of the second or passing lane.

However, observation of the cores cut from the relatively dry concrete in the first (traffic) lane and from the wetter concrete in the second (passing) lane, as well as of the concrete adjacent to the side headers did not disclose any

TABLE 3
AVERAGE CONCRETE COMPRESSIVE STRENGTH TESTS FAIRFIELD TEST HIGHWAY 5-SACK CONCRETE

(1) 6- by 12-in. Field Cylinders—Compressive Strength in psi. (Figures are the average of all cylinders cast each day)

Date Cons.	Average Temperature		Age			
	Conc.	Air	3 days	10 days	28 days	1 year
Traffic Lane						
	deg. F.	psi.	psi.	psi.	psi.	psi.
5-23-49 AM	85	96	2180	3240	4330	6105
5-24-49 AM	83	88	2180	3715	4730	6105
5-25-49 PM	100	99	2180	3145	4130	6105
Ave. Tr. Lane	89	91	2180	3367	4997	6105
Passing Lane						
6-7-49 PM	89	85	1525	2675	4005	5315
6-8-49 AM	80	71	1525	2995	4270	5315
Ave. Pass. Lane	85	78	1525	2835	4138	5315

(2) 5- by 8-in. Beam Ends (Modified Cube)

Traffic Lane						
5-24-49 AM	83	88	2850	4330	5515	6310
Passing Lane						
6-8-49 AM	80	71	1980	3325	4720	5320

(3) Cores from Pavement—Compressive Strength in psi (Figures are the average of all cores each day)

Traffic Lane						
5-23-49 AM	85	96			5060	6510
5-24-49 AM	83	88			4725	6005
5-25-49 PM	100	99			4665	6245
Ave. Tr. Lane	89	91			4817	6253
Passing Lane						
6-7-49 PM	89	85			3855	4750
6-8-49 AM	80	71			3850	5035
Ave. Pass. Lane	85	78			3853	4968

material deficiency in placement of any of the concrete, regardless of consistency.

Concrete Strength—As will be noted from a study of the compressive, modulus of rupture and tension tests the concrete was of good quality throughout although there is a marked difference in strength between the earlier built traffic lane and the later built passing lane (Tables 3 and 4).

As previously stated this difference probably was due to the fact that the temperature of air and concrete during the construction of the earlier build traffic lane was greater and the water cement ratio lower than during the construction of the second (passing) lane.

The effects of the lower strengths are not appreciably apparent to date in the pavement performance, the crack incidence being substantially the same in either lane. It would, therefore, appear that differences in strength

TABLE 4
AVERAGE MODULUS OF RUPTURE AND TENSION TESTS FAIRFIELD TEST HIGHWAY 5-SACK CONCRETE

(1) Modulus of Rupture—(5- by 6- by 31-in. Beams).

Date Cons.	Average Temperature		Age at Test			
	Conc.	Air	3 days	10 Days	28 Days	1 Year
Traffic Lane						
	deg. F.	psi.	psi.	psi.	psi.	psi.
5-24-49	83	88	470	625	675	810
Passing Lane						
6-8-49	80	71	355	505	625	685

(2) Tension (6- by 10-in. Cylinders)

Date Cons	Average Temperature		Age at Test					
	Conc	Air	12 Hrs	24 Hrs	48 Hrs.	3 Da	10 Da.	28 Da.
Traffic Lane								
	deg. F.	psi	psi	psi	psi	psi	psi	psi.
5-24-49	83	88	105	136	184	215	295	327
Passing Lane								
6-8-49	80	71	41	72	123	155	255	284

of the order noted are insufficient to effect any measurable differences in concrete performance, at least up to the period covered by this report (1½ years).

Tension Test Equipment and Procedure—In an effort to determine the tensile strength of the concrete at early ages (12, 24 and 48 hr.) a special type of test specimen and field testing equipment was designed.

The test specimens consisted of 6- by 10-in. concrete cylinders cast in standard 6- by 12-in. split steel molds with facilities for accurately

placing and aligning two $\frac{3}{8}$ -in. carriage type bolts with specially machined heads abutting at the mid-point in the specimen. Soft rubber tubes were placed over the greater portion of the rods to minimize bond with the surround-




Figure 12. Open Space Left in Reinforcing Steel for Cutting Core




Figure 13. Molds for Making Tensile Strength Test Specimens

ing concrete as well as to assist in eliminating any eccentricity in alignment during the application of the load (Fig. 13).

Holes were drilled in the bolt heads for the insertion of a pin to maintain alignment and prevent movement during fabrication.

A special breaking machine was built for the early age field tests (Fig. 14).

Crack Record—Initial shrinkage crack records were made early in the morning following each day's pour. As anticipated numerous transverse cracks have developed (Figs. 16, 17 and 18). This report includes the crack record up to one year at which time the average number of cracks per 100 ft. of pavement equaled 22 with an average slab length of 4.5 ft. except for the first 140 ft. from each end, where the slab lengths were substantially greater.




Figure 14. Field Equipment for Breaking Tensile Test Specimens

As will be noted in the crack record diagrams (Fig. 16) the slab lengths were greater just before the construction joint at the end of each day's pour but quite short at the start of the next day's pour, notwithstanding the continuity of the reinforcing across the construction joint (Figs. 16 and 19).

Roughness Measurements—Initial and subsequent pavement roughness measurements were made with the Hveem Profilometer and by Professor Moyer with equipment developed under his direction at the Institute of Transportation and Traffic Engineering of the University of California, Berkeley. See Figure 20




Figure 15. Typical Fractures of Tensile Test Specimens

for typical profilograph (morning and afternoon) recorded by the Hveem Profilometer.

Comparative Cost Studies—Following is a comparison of the cost per mile of a 12-ft. lane of an unreinforced and a reinforced concrete pavement slab of the thickness and percentages of reinforcement in the Fairfield Test

Highway at the project bid prices per cubic yard of concrete (\$14.00) and per pound of steel in place (\$0.08):

1. Unreinforced.....	\$21,896.00
2. Reinforced with 1/2-in. bars 4-in. c. (0.62%)....	\$33,317.00
3. Reinforced with 3/4-in. bars 5-in. c. (0.50%)....	\$31,227.00

It would, therefore, appear that reinforcement to control cracking is probably not

economical and cannot be justified unless an equivalent benefit is attained with relation to long-time riding qualities and greater dura-

In this connection the cost data in Table 5 are of interest. All figures are based on the unit bid prices for the Fairfield Test Project.




Figure 16. Crack Formation during First Year

bility or the slab thickness and the supporting base can be modified sufficiently to offset the added cost of the reinforcing.

From Table 5 it will be noted that a 6-in. reinforced concrete base (0.5 percent Steel—6.5 in. c/c) with a 4-in. Cement Treated




Figure 17. Average Slab Lengths




Figure 18. Average Slab Length and Number of Cracks Formed per 100 ft. at Age of 1 Yr.

Selected Material Base compares in cost with an 8-in. unreinforced slab with the 10-in. select material base of which the top 4-in. was cement treated.

Additional projects designed to compare the performance of the above alternate designs as

well as other competitive designs appear in order.

Summary—Owing to the comparatively short period which has elapsed since the construction of the project described in this report there

are few conclusions which can be reached with assurance at the present time.

The crack incidence is high in a continuously reinforced slab of the design and length of this project (one mile without substantial expansion or shrinkage relief).

These cracks, although not wide at present may subsequently develop decidedly adverse and objectionable characteristics. In a few cases they have already done so.

To avoid numerous shrinkage cracks it appears necessary to break the continuity of the reinforcing at relatively short intervals—say 100 to 200 ft. This checks with experience elsewhere.³

Whether or not expansion joints should be provided or weakened planes at the breaks in continuity of reinforcing is not apparent from test data to date, at least under California climatic conditions.

Obviously atmospheric temperature conditions during and immediately following construction is an important factor.

The California project was constructed in the summer and under relatively high atmospheric temperature conditions. Much higher subsequent shrinkage and consequent higher crack incidence could be anticipated than had the construction been carried on during the lower temperature conditions which prevail during the late fall, winter and early spring months.

³ 10 Year Progress Report by Cashell and Benham on the Indiana Test Highway, *Proceedings*, Highway Research Board, Vol. 29 (1949).

The effect of time of day and (or) order of construction also is apparent from the crack development at the construction joints where even though the reinforcing steel is carried continuously across the construction joint the crack incidence is much less at the end of the day's run, just before reaching the construction joint, than during the first hour of the succeeding day when the incidence is somewhat greater than the average.

Up to one and one half years the crack incidence was not materially affected by the percentage of steel, the incidence being substantially the same for the 0.50 percent—5-in. spaced high yield bars as for the 0.62 percent—4-in. spaced standard medium yield bars.

Furthermore, the crack development at 18 mo. was apparently not influenced appreciably by differences in early concrete strengths of the order observed on the Fairfield project.

ACKNOWLEDGEMENTS

The author wishes to express appreciation to the staff of the Materials and Research Department for their assistance; particularly to Associate Electrical Engineer J. E. Barton who had charge of the installation of the strain gages and other pavement movement and strain measurement units and the subsequent measurements, recordings and analysis of the strain test data, etc.; also to Associate Materials and Research Engineer L. P. Kovanda who had charge of all work relating to concrete mixture design and concrete tests, including analysis of the concrete test data.